

IOWA DEPARTMENT OF NATURAL RESOURCES
LAND & WATERS BUREAU
WALLACE STATE OFFICE BUILDING

ADDENDUM No.1

CENTER LAKE
FISH BARRIER SYSTEM & SHORELINE RESTORATION
DICKINSON COUNTY
PROJECT NUMBER 15-01-30-05
BID DATE: AUGUST 18, 2016
ISSUE DATE: August 15, 2016

This Addendum is issued to modify, explain or correct the original Drawings and Specifications, and is hereby made a part of the Contract Documents. Please attach this Addendum to the Project Manual in your possession. Insert the number and issue date of this Addendum in the blank space provided on the Bid Form.

Specifications:

- A. Technical Specification Section 33 42 13 - Culverts, Part 2.1, Section B.2 shall be deleted and replaced with the following:
Gage: 16 gage for 15 inch diameter, 12 gage for 36 inch diameter.
- B. Technical Specification Section 33 43 00 - Water Control Structures, Part 2.1, Section B.1: Inlet Pipe, Part b shall be deleted and replaced with the following:
Material: Corrugated Metal Pipe (CMP), zinc coated, 12 gage, 2-2/3" x 1/2" corrugation
- C. Technical Specification Section 33 43 00 - Water Control Structures, Part 2.1, Section B.2: Riser, Part b shall be deleted and replaced with the following:
Material: CMP, zinc coated, 10 gage, 3" x 1" corrugation
- D. Technical Specification Section 33 43 00 - Water Control Structures, Part 2.1, Section B.6: Outlet Pipe, Part b shall be deleted and replaced with the following:
Material: Corrugated Metal Pipe (CMP), zinc coated, 12 gage, 2-2/3" x 1/2" corrugation

All other terms and conditions remain unchanged.