

IOWA DEPARTMENT OF NATURAL RESOURCES
LAND & WATERS BUREAU
WALLACE STATE OFFICE BUILDING

ADDENDUM No. 4

HICKORY GROVE LAKE
MECHANICAL DREDGING & SHORELINE ARMORING
STORY COUNTY, IOWA
PROJECT NUMBER: 16-02-85-05

November 13, 2018

This Addendum is issued to modify, explain or correct the original Drawings and Specifications, and is hereby made a part of the Contract Documents. Please attach this Addendum to the Project Manual in your possession. Insert the number and issue date of this Addendum in the blank space provided on the Proposal Form.

Stage Lake Volume

- A. The units in the Stage Lake Volume table that was included in Addendum 2 are incorrect. Attached is the corrected table.

Hickory Grove Lake - 4,382 acre watershed			
Stage Lake Volume			
Elevation (feet)	Volume (acre-feet)	Volume (cubic yards)	Volume (cubic feet)
970	1,209.8	1,951,811	52,698,888
969	1,134.9	1,830,972	49,436,244
968	1,061.0	1,711,747	46,217,160
967	988.0	1,593,973	43,037,280
966	916.0	1,477,813	39,900,960
965	845.6	1,364,235	36,834,336
964	778.8	1,256,464	33,924,528
963	715.5	1,154,340	31,167,180
962	655.5	1,057,540	28,553,580
961	600.4	968,645	26,153,424
960	548.0	884,107	23,870,880
959	498.1	803,601	21,697,236
958	450.4	726,645	19,619,424
957	404.9	653,239	17,637,444
956	362.9	585,479	15,807,924
955	323.7	522,236	14,100,372
954	287.1	463,188	12,506,076
953	253.1	408,335	11,025,036
952	221.8	357,837	9,661,608
951	192.5	310,567	8,385,300
950	165.2	266,523	7,196,112
949	140.5	226,673	6,120,180
948	118.1	190,535	5,144,436
947	97.5	157,300	4,247,100
946	78.5	126,647	3,419,460
945	61.8	99,704	2,692,008
944	46.7	75,343	2,034,252
943	33.1	53,401	1,441,836
942	21.2	34,203	923,472
941	12.0	19,360	522,720
940	5.1	8,228	222,156