

IOWA DEPARTMENT OF NATURAL RESOURCES
LAND & WATERS BUREAU
WALLACE STATE OFFICE BUILDING

ADDENDUM No. 1

PLEASANT CREEK STATE RECREATION AREA
PHASE 1 - PCC PARKING LOT PAVING
LINN COUNTY, IOWA
PROJECT NUMBER: 19-06-57-04

MAY 20, 2019

This Addendum is issued to modify, explain or correct the original Drawings and Specifications, and is hereby made a part of the Contract Documents. Please attach this Addendum to the Project Manual in your possession. Insert the number and issue date of this Addendum in the blank space provided on the Proposal Form.

Plans:

- a. Sheet D.04
 - i. Waterborne and solvent borne paint are both acceptable for striping.
- b. Sheet M.02
 - i. The SW-512 has a rim elevation of 826.5 and is 18" in diameter. Minor shaping around the manhole is require to bring the grade down to the rim elevation. Payment for shaping is incidental to Bid Item 19.
 - ii. The SW-513 has a rim elevation of 823.3.

Specifications:

- a. Compaction testing will consist of proof rolling.
- b. Concrete testing will be handled by the DNR.
- c. Contactor is required to remove the silt fencing once the seeding is established.
- d. Erosion control silt fencing will be paid at the unit price per the measured quantity.