IOWA DEPARTMENT OF NATURAL RESOURCES LAND & WATERS BUREAU WALLACE STATE OFFICE BUILDING

ROCK CREEK STATE PARK SANITARY SEWER LINING JASPER COUNTY, IOWA PROJECT NUMBER: 21-05-50-03

Date 10/13/2022

This Addendum is issued to modify, explain or correct the original Drawings and Specifications, and is hereby made a part of the Contract Documents. Please attach this Addendum to the Project Manual in your possession. Insert the number and issue date of this Addendum in the blank space provided on the Proposal Form.

GENERAL CLARIFICATION

All of the host pipe is Clay Tile and all segments are 6-inch in diameter.

Plans:

A. Sheet 7
Segment from MH 4 to MH 5 needs to be lined.

- B. Sheet 12
 - i) Segment from MH 10 to MH 11 needs to be lined.
 - ii) Replace the first callout nearest to Manhole 10 on Sheet 12 with

"POINT REPAIR MH10 – MH11 REPLACE PIPE STARTING FROM MH 10 TO 8FT. WITH 6" PVC SDR 35 PIPE"