IOWA DEPARTMENT OF NATURAL RESOURCES
LAND & WATERS BUREAU
6200 Park Ave., Ste. 200, Des Moines, IA 50312

ADDENDUM No. 1

IOWA STATE FOREST NURSERY – SEED BUILDING ADDITION
STORY COUNTY, IOWA
PROJECT NUMBER: 24-02-85-01

September 14, 2026

This Addendum is issued to modify, explain or correct the original Drawings and Specifications, and is hereby made a part of the Contract Documents. Please attach this Addendum to the Project Manual in your possession. Insert the number and issue date of this Addendum in the blank space provided on the Proposal Form.

Specifications:

1. Substitution request: Specification Section 233423
    1. All HVAC equipment shall be approved for use via submittal prior to ordering and installation. All equipment and all manufacturers meeting specified performance and warranty requirements will be considered during submittal review.
2. Substitution Request: Specification Section 238240
    1. 2.01 Manufacturers – **ADD** 2.01 A 4. Ouellet, 5. King Electric, 6.Brasch, and 7. Indeeco
3. Substitution Request: Specification Section 265100
    1. All electrical equipment shall be approved for use via submittal prior to ordering and installation. All equipment and all manufacturers meeting specified performance and warranty requirements will be considered during submittal review.
4. Specification Section 133400: **DELETE** 2.05 E. and **ADD** 2.05 E. Metal Roof Panels: 1. Basis of Design: a. Exposed-fastener metal roof panels, rolled R-panel with raised ribs and recesses. Material: Galvalume steel sheet, 24 Gauge minimum, PVDF coated.

Plans:

1. All concrete slabs to be 6-inch thickness. 5-inch slab thicknesses shown on plans, in specifications or details are incorrect.
2. Location of electrical panel boxes on plans is incorrect. Please allow for 50 additional feet of service line to connect to electrical panels.