

Memorandum

Foth Infrastructure & Environment, LLC 411 6th Ave SE, Suite 400 Cedar Rapids, IA 52401 (319) 365-9565 foth.com

March 27, 2024

TO: Kenneth Miller, DMASWA

CC:

FR: Brian Harthun, Foth

RE: 2024 Closure/Post Closure Costs

Attached is the updated engineering estimate for the Closure/Post Closure Cost estimate for Cells 1-9 including the abutment liner in Cell 9. Reviewing the 2023 unit costs and comparing it to the IDNR published Inflation Factor of 1.026 date January 25, 202, Foth recommends using the inflation factor to adjust the Closure/Post Closure Costs.

Below is the adjusted Closure Post Closure Cost utilizing the Inflation Factor. The total increase from 2023 to 2024 is \$187,077.48. Attached separately is the breakdown of the Closure/Post Cost Estimate.

| DMASWA Closure/Post Closure Cost Estimate | | | | | |
|---|-------------|-------------|--|--|--|
| 2022 2023 | | | | | |
| Closure Cost | \$4,542,350 | \$4,660,508 | | | |
| Post Closure Cost | \$2,649,812 | \$2,718,732 | | | |
| Total | \$7,192,162 | \$7,379,239 | | | |

ased on the updated site topography survey and updated density calculations, there is approximately 15.1 years of life based on a remaining air space of 2,375,386 in tons, an average annual rate of 153,497 tons, and the averaged compaction rate of 1,534 tons per cubic yard. Below is the table and graph showing the compaction rates overtime and the remaining airspace.

1




Dubuque Metropolitan Area Solid Waste Agency Landfill Cell 9 Design Capacity Cell 9 + Abutment 1 Volume Used/Period Reporting Period Amount of MSW/Period **Yearly Rate Total Air Remaining** Date of Survey (Days) (Tons) (Tons/year) Density (lbs/cy) Space (cy) (cy) 1/7/2016 174 63,009 132,174 106,000 1,189 4,710,081 6/29/2016 141 56,914 147,331 87,510 1,301 4,622,571 11/17/2016 166 144,001 92,826 1,411 4,529,745 65,491 5/2/2017 197 88,484 163,942 145,322 1,218 4,384,423 11/15/2017 365 140,091 140,091 198,253 1,413 4,186,170 11/15/2018 369 173,193 171,316 240,067 1,443 3,946,103 11/19/2019 346 155,988 164,554 223,825 1,394 3,722,278 10/30/2020 334 150,880 164,884 197,887 1,525 3,524,391 9/29/2021 172,699 237,328 374 176,957 1,491 3,287,063 10/8/2022 389 185,419 173,979 191,540 1,936 3,097,588 11/1/2023 Total 2,855 1,071,007 157,497 1,720,558 1,534 3,097,588

Remaining Air Space

| Tons | 2,375,386.82 |
|-------|--------------|
| Years | 15.08 |







Municipal Solid Waste Sanitary Landfill Financial Assurance Report Form

SECTION 1: FACILITY INFORMATION

(please print or type)

| Information Requested | | | | | | |
|-----------------------|------------|--|----------------|--------------|--|--|
| Facility Name: | Dubuque | Metropolitan Area Solid Waste Agency | Permit Number: | 31-SDP-02-75 | | |
| Permitted Agend | cy/Entity: | Dubuque Metropilitan Area Solid Waste Agency | | | | |

SECTION 2: CLOSURE/POSTCLOSURE OR CORRECTIVE ACTION COST ESTIMATES

| Information Requested | Cost Estimate | Date of Cost Estimate | | |
|--|---------------|-----------------------|--|--|
| Updated Closure Cost Estimate | \$ 4,660,508 | 3/25/2023 | | |
| Updated Postclosure Cost Estimate | \$ 2,718,732 | 3/25/2023 | | |
| Initial or Updated Corrective Action Cost Estimate | \$ 12,300 | 5/25/2022 | | |

^{*}Attach closure/postclosure cost estimate(s) signed and certified by an Iowa-licensed professional engineer. Cost estimates shall include, at a minimum, each of the cost line items defined in 113.14(3)"c" for closure and 113.14(4)"c" for postclosure. Please provide closure and/or postclosure site area acreage information with the estimates.

Provide a cost estimate for corrective action only if corrective action is required and a corrective action plan has been approved by the Department. Attach the corrective action cost estimate signed and certified by an lowa-licensed professional engineer. The cost estimate shall account for total costs of the activities described in the approved corrective action plan for the corrective action period.

SECTION 3: FACILITY WASTE TONNAGE INFORMATION

| Information Requested | Tons |
|---|--------------|
| Remaining permitted capacity as of the beginning of permit holder's current fiscal year | 2,375,386.82 |
| Amount of waste disposed of at the facility during the prior fiscal year | |

SECTION 4: PROOF OF COMPLIANCE

| (ATTACH AUDIT REPORT) |
|-----------------------|
| |
| |
| |
| |

Privately Owned Municipal Solid Waste Landfills

(ATTACH AFFIDAVIT)

Attach owner/operator's affidavit indicating that an annual review has been performed by a certified public accountant to determine whether the privately owned landfill is in compliance with IAC 567 Chapter 113. The affidavit shall state the name of the certified public accountant, the dates and conclusions of the review, and the steps taken to rectify any deficiencies identified by the accountant.

SECTION 5: FINANCIAL ASSURANCE INSTRUMENT

Type and Value of Financial Assurance Instrument(s) (ATTACH INSTRUMENT(S))

| Assurance Instrument | Establishment Date | Mechanism Covers | Instrument Value* |
|---|--------------------|---|-------------------|
| Trust Fund | | Closure 🗌 | |
| 567 IAC 113.14(6)"a" | | Postclosure 🗌 | \$ |
| | | Corrective Action | |
| Curaty Dand | | Closure 🗌 | |
| Surety Bond 567 IAC 113.14(6)"b" | | Postclosure 🗌 | \$ |
| | | Corrective Action | |
| Latter of Coadh | | Closure 🗌 | |
| Letter of Credit 567 IAC 113.14(6)"c" | | Postclosure | \$ |
| | | Corrective Action 🗌 | |
| | | Closure 🗌 | |
| Insurance 567 IAC 113.14(6)"d" | | Postclosure | \$ |
| 307 INC 113.1 1(0) U | | Corrective Action | |
| | | Closure 🗌 | |
| Corporate Financial Test 567 IAC 113.14(6)"e" | | Postclosure | \$ |
| 307 INC 113.1 1(0) C | | Corrective Action | |
| | | Closure 🗌 | |
| Local Gov't. Financial Test 567 IAC 113.14(6)"f" | | Postclosure | \$ |
| 307 110 11011 1(0) | | Corrective Action | |
| | | Closure 🗌 | |
| Corporate Guarantee 567 IAC 113.14(6)"g" | | Postclosure | \$ |
| 307 INC 113.14(0) 8 | | Corrective Action | |
| | | Closure 🗌 | |
| Local Gov't Guarantee 567 IAC 113.14(6)"h" | | Postclosure | \$ |
| | | Corrective Action | |
| Local Gov't. Dedicated Fund 567 IAC 113.14(6)"i" | | Closure 🔀 | |
| | 12/15/1997 | Postclosure $oxtimes$ | \$ 5,476,405.58 |
| 307 IAC 113.14(0) I | | Corrective Action $igtigtigtigtigtigtigtigta$ | |

Section 6: Initial Proof of Establishment of Accounts

Pursuant to IAC 567 Chapter 113.14(8)"f", documentation of the establishment of accounts is to be submitted to the department by April 1, 2003 for currently permitted MSWLFs. Permit holders for MSWLFs permitted after April 1, 2003, shall submit documentation of the establishment of accounts prior to the MSWLF's initial receipt of waste.

^{*}Pursuant to IAC 567 113.14(9), if account(s) are restricted/reserved to pay for closure, postclosure or corrective action costs, then the amount of the financial assurance instrument may be reduced by the sum of the cash balance of the account(s) established to comply with subrule 113.14(8).

Please attach documentation indicating accounts/fund have been established for closure and postclosure care and if the account(s) are restricted/reserved for closure or postclosure care. Examples of documentation include bank statements for closure/postclosure accounts, letter signed by the chief financial officer, letter from certified public accountant, etc.

Accounts established pursuant to paragraph 113.14(6)"a" for trust funds or paragraph 113.14(6)"i" for local government dedicated funds also satisfies the requirements of this subrule, and the permit holder shall not be required to establish additional closure and postclosure accounts.

SECTION 7: CLOSURE AND POSTCLOSURE ACCOUNTS

Completion of the following closure and postclosure account information complies with the annual financial statement requirements of IAC 567 113.14(3)"a" and 113.14(4)"a" by indicating the current balance(s) of the closure/postclosure account(s) or dedicated/trust fund and the projected amount(s) to be deposited in the account(s).

Under "Beginning Balance", please state the account/fund balance 30 days after the start of the previous fiscal year, for "Ending Balance", indicate the account balance 30 days after the close of the previous fiscal year, and for "Projected Deposit", indicate the amount to be deposited within 30 days of the close of the permit holder's fiscal year.

| Information Requested | Beginning Balance | Ending Balance | Projected Deposit | | | | |
|---|-------------------|-----------------|-------------------|--|--|--|--|
| Closure Account Balance (see formula below) | \$ | \$ | \$ | | | | |
| Postclosure Account Balance (see formula below) | \$ | \$ | \$ | | | | |
| Or | | | | | | | |
| Dedicated Fund Balance (see formula below) | \$ 5,476,405.58 | \$ 5,666,688.92 | \$ 190,283.34 | | | | |
| Trust Fund Balance (see formula below) | \$ | \$ | \$ | | | | |

Formula for Projected Deposits

Closure or Postclosure Account

Where "CE" is the closure or postclosure cost estimate, "CB" is the balance 30 days after close of the previous fiscal year, "RPC" is the remaining permitted capacity in tons, of the landfill from the beginning of the current fiscal year, and "TR" is the total number of tons of solid waste disposed in the prior year.

Dedicated/Trust Fund

Where "CE" is the closure or postclosure cost estimate, "CB" is the balance 30 days after close of the previous fiscal year, and "Y" is number of years remaining in the pay-in period.

If needed, the space below can be used to show calculations for projected deposits

| · · · · · · · · · · · · · · · · · · · | · · · · · · · · · · · · · · · · · · · |
|---------------------------------------|---------------------------------------|
| Closure | Postclosure |
| | |
| | |
| | |
| | |

SECTION 8: PERMIT HOLDER ENDORSEMENT

Submittal of this completed and endorsed form along with all required documentation establishes Notification and Proof of Permit Holder Compliance with IAC 567 Chapter 113.

| Name of Official: Kenneth M. Miller | | | Title: | Solid Wa | aste Agency Administrato | r |
|--|--------|----|--------|----------|--------------------------|---|
| Agency/Entity:Dubuque Metropolitan Area Soild Waste Ag | gency | | | | | |
| Address: 925 Kerper Ct. | | | | | | |
| City: _Dubuque | State: | IA | | | Zip: <u>52001</u> | |
| Telephone: _(563) 589-4354 | Fax: | | | | | |
| Email Address: kmiller@cityofdubuque.org | | | | | | |
| Signature of Official: | | | | _ Date: | 3/29/2024 | |
| 7 | | | | | | |

Questions? Contact Chad Stobbe at (515) 201-8272 or Chad.Stobbe@dnr.iowa.gov

3/25/2024

FOR THE

Dubuque Metropolitan Area Solid Waste Agency

DUBUQUE, IOWA

March 25, 2024

Permit No. 31-SDP-2-75P



DUBUQUE FIANACIAL ASSURANCE COST ESTIMATE March 25, 2023

| March 23, 2023 | | | Closi | Date of Update Closure/Post Closure Update Year | | 3/25/2024 2024 | | |
|----------------------------|----------|-----------|-------|--|----------------|-------------------|----|---------|
| Closure Cost Estimate | | | I | nflation Fa | ector 1.026 | | | |
| Decription | Quantity | Unit | Un | it Cost | Extension | 1 | | 2024 |
| Cells 4-8 | | | | | | | | |
| 1 R and D Cap | | 30.7 Acre | \$ | 28,053 | \$ | 861,239 | | |
| 2 Engineering/Permitting | | 1 Each | \$ | 86,584 | \$ | 86,584 | | |
| | | | | | Subtotal | | \$ | 947,823 |
| Cell 9 Phase 1 | | | | | | | | |
| 3 Grading Layer | | 10 Acres | \$ | 1,863 | \$ | 18,628 | | |
| 4 60-mil HDPE Cap | | 10 Acres | \$ | 50,287 | \$ | 502,871 | | |
| 5 Vegetative Layer | | 10 Acres | \$ | 5,587 | \$ | 55,873 | | |
| 6 Seeding | | 10 Acres | \$ | 1,848 | \$ | 18,475 | | |
| 7 Erosion Control | | 1 Each | \$ | 28,862 | \$ | 28,862 | | |
| 8 Engineering/Permitting | | 1 Each | \$ | 57,722 | \$ | 57,722 | | |
| | | | | | Subtotal | | \$ | 682,432 |
| Cell 9 Phase 2 | | | | | | | | |
| 9 Grading Layer | | 11 Acres | \$ | 7,450 | \$ | 81,952 | | |
| 10 60-mil HDPE Cap | | 11 Acres | | 50,287 | | 553,159 | | |
| 11 Vegetative Layer | | 11 Acres | | 4,471 | \$ | 49,176 | | |
| 12 Seeding | | 11 Acres | | 1,848 | \$ | 20,323 | | |
| 13 Erosion Control | | 1 Each | \$ | 28,862 | \$ | 28,862 | | |
| 14 Engineering//Permitting | | 1 Each | \$ | 57,722 | \$ | 57,722 | | |
| | | | | ŕ | Subtotal | , | \$ | 791,192 |
| Cell 9 Phase 3 | | | | | | | | |
| 15 Grading Layer | | 10 Acres | \$ | 7,450 | \$ | 74,501 | | |
| 16 60-mil HDPE Cap | | 10 Acres | | 50,287 | \$ | 502,871 | | |
| 17 Vegetative Layer | | 10 Acres | | 4,471 | \$ | 44,705 | | |
| 18 Seeding | | 10 Acres | \$ | 1,848 | \$ | 18,475 | | |
| 19 Erosion Control | | 1 Each | \$ | 28,862 | \$ | 28,862 | | |
| 20 Engineering//Permitting | | 1 Each | \$ | 57,722 | \$ | 57,722 | | |
| | | | | | Subtotal | | \$ | 727,137 |
| Cell 9 Phase 4 | | | | | | | | |
| 16 Grading Layer | | 11 Acres | | 7,450 | \$ | 81,952 | | |
| 17 60-mil HDPE Cap | | 11 Acres | | 50,287 | \$ | 553,159 | | |
| 18 Vegetative Layer | | 11 Acres | | 4,471 | \$ | 49,176 | | |
| 19 Seeding | | 11 Acres | | 1,848 | \$ | 20,323 | | |
| 20 Erosion Control | | 1 Each | \$ | 28,862 | \$ | 28,862 | | |
| 21 Engineering//Permitting | | 1 Each | \$ | 57,722 | \$ Subtatal | 57,722 | \$ | 791,192 |
| Abutment Area Cell 9 | | | | | Subtotal | | | |
| 22 Grading Layer | | 9.9 Acres | \$ | 7,450 | \$ | 73,756 | | |

| Post Closure | 23 60-mil HDPE Cap 24 Vegetative Layer 25 Seeding 26 Erosion Control 27 Engineering//Permitting Cost Estimate | | 9.9 Acres 9.9 Acres 9.9 Acres 1 Each 1 Each | \$ \$ \$ \$ | 50,287 4,471 1,848 28,862 57,722 | \$ \$ \$ \$ \$ Subtota | 497,843 44,258 18,291 28,862 57,722 | \$ \$ | 720,732 4,660,508 |
|-------------------------------------|--|----------|---|--------------------------------|--|------------------------|---|-----------------|-----------------------------|
| | Decription | Quantity | Unit | Extension | | | | | |
| | 1 Cap Maintenance | | 30 events | \$ | 26,553 | \$ | 796,580 | | |
| | 2 GW Monitoring | | 30 events | \$ | 57,722 | \$ | 1,731,660 | | |
| | 3 Inspections | | 60 events | \$ | 1,732 | \$ | 103,916 | | |
| | 4 Leachate Disposal | | 30 events | \$ | 2,886 | \$ | 86,575 | | |
| | | | | Total Post Closure Cost | | | | \$ | 2,718,732 |
| Total Closure/Post Closure Estimate | | | | | | | | \$ | 7,379,239 |